

Windsong Farm Golf Club Parking Lot and Practice Facility Improvements Independence, Project #2018-13

Project Overview: This project will take place on the golf course property on both sides of CR 6. They propose to reconstruct their existing practice facility and clubhouse service access road, reconstruct their existing main parking lot and construct a new event overflow parking lot. Commission Rules that apply to this work will include Rule D (stormwater management) and Rule E (Erosion and Sediment Control).

Applicant: Windsong Farm Golf Club, Attn. Jon Dailing, 18 Golf Walk, Independence, MN 55359. Phone: 952-797-3727. Email; jdailing@wsfarm.com

Agent/Engineer: EOR Inc., Attn. Derek Lash, 7030 6th St. N., Oakdale, MN 55128. Phone; 651-203-6031. Email; dlash@eorinc.com

Exhibits:

- 1) PSCWMC Request for Plan Review, received September 11, 2018.
- 2) Fees for \$1,675 for 15.48 acres of disturbance for grading and erosion control and 1.237 acres of new impervious areas water quality/quantity.
- 3) Windsong Farm Golf Club construction Plans for 2018 Parking Lot and Golf Course Practice Facility Improvements by Duininck Inc. dated September 6, 2018
 - a. Sheet 1 of 11, Title Page
 - b. Sheet 2 and 3 of 11, Demo Plan,
 - c. Sheet 4 of 11, Site and Surfacing Plan, Main Parking Lot
 - d. Sheet 5 of 11, Site and Surfacing Plan, Overflow Parking Lot updated October 3, 2018.
 - e. Sheet 6 of 11, Grading and Drainage Plan Main Parking Lot.
 - f. Sheet 7 of 11, Grading and Drainage Plan Overflow Parking Lot, updated October 3, 2018.
 - g. Sheets 8 to 10 of 11 Windsong Golf Club Stormwater Pollution Prevention Plan. (sheet 10 of 11, Entire Site Erosion Control Plan by Duininck Inc. dated October 3, 2018)
 - h. Sheet 11 of 11 Phasing Plan
- 4) Windsong Golf Club, Practice Facility Plans by John Faught Design, dated August 27, 2018.
 - a. Sheet 1 of 6, Site Plan
 - b. Sheet 2 of 6, Area of Disturbance Plan
 - c. Sheet 3 of 6, Grading and Drainage Plan
 - d. Sheet 4 of 6 Earthwork Plan

GREENFIELD • INDEPENDENCE • LORETTO • MAPLE PLAIN • MEDINA • MINNETRISTA

Windsong Farm Golf Club Parking Lot and Practice Facility Improvements 2018-13, Independence October 15, 2018

- e. Sheet 5 of 6, Grassing Plan
- f. Sheet 6 of 6, Construction Details.
- 5) Windsong Practice Facility Expansion Stormwater Management Plan Narrative and HydroCAD model by EOR Inc., Narrative dated September 6, 2018, revised October 3, 2018. HydroCAD model dated October 3, 2018.

Findings;

- 1) A complete application was received September 11, 2018. Updated overflow parking location change details received October 3, 2018. The initial 60-day period for a PSCWMS decision, per MN Statute 15.99 expires November 10, 2018.
- 2) Actual project review fee should be \$1,550 (15.48 acres of disturbance for grading fee and 1.237 ac. of new impervious area for water quality fee). \$125 refund is due.
- 3) A breakdown of the work proposed is as follow;
 - a. The practice facility work will disturb 12.3 acres for reconstruction of practice tees, greens, bunkers, and drainage infrastructure. 9,500 sq. ft. of existing cart path will be removed and replaced with 36,700 sq. ft. of new path and 2,250 sq. ft. of new impervious artificial tee areas. For site analysis, new imperious areas from this portion of the work will amount to 18,850 sq. ft.
 - i. This water will be routed over a filter swale and then into an existing detention basin for rate and quality controls.
 - b. The main parking area work will disturb 1.15 acres. The asphalt surface will be milled and overlaid with some additional parking spaces and islands constructed. New impervious areas from this portion of the work will be 7,925 sq. ft.
 - i. This water will be routed over a filter swale and then into an existing detention basin for rate and quality controls.
 - c. The work on the clubhouse service access road will disturb 0.51 acres. It will actually reduce its current impervious footprint by 512 sq. ft.
 - i. Stormwater management improvements for this portion of the work will consist of routing the water over a filter swale area before it runs into an existing irrigation pond.
 - d. Construction on the event parking lot will disturb 1.4 acres. 2,536 sq. ft. of existing gravel road will be removed and replaces with 19,009 sq. ft. of new gravel and paved parking areas. An additional 25,600 sq. ft. of new turf (pervious) parking area will also be constructed as part of this work. The net amount of new impervious areas from this work will be 16,473 sq. ft.
 - i. Stormwater management proposed for this area by directing the impervious area over the new turf parking lot. The turf parking lot will have engineered soils, that in effect treat the impervious areas by filtration and increasing distance the impervious area flows over grass/amended soil areas. This combination of distance of travel and amended soils will treat the water before it leaves the site.

Stormwater Management

- 1) The area on the north side of CR 6 will drain into Fox Lake. The area south of CR 6 drains into the Pioneer Creek.
- 2) Land use will remain the same on the south side of the project. The event overflow parking on the north side is currently cropland.
- 3) The project proposes to direct the water from the impervious areas over filtration swales, engineered overflow parking areas with turf /filtration and into an existing irrigation pond and detention pond.
- 4) Based on the site design, the project will meet the Commission's flow rate requirements. They will be as follows;

	2-yr (cfs)		10-yr (cfs)		100-yr (cfs)	
	Existing	Proposed	Existing	Proposed	Existing	Proposed
Practice Facility	2.2	2.2	6.8	6.3	11.5	11.1
Clubhouse Area	1.2	0.8	2.1	1.4	4.2	2.5
Event Parking Lot	2.8	0.3	5.6	0.7	12.1	7.3

- 4) Total phosphorus and suspended solids will be reduced after development without the need for ponding or basins based on; a) the change in the land use from agriculture/open areas to golf course/open areas, b) the new impervious areas are linear (cart path) that do not concentrate runoff and c) designed water flows over vegetation areas.
 - a. This design will essentially route the water over vegetation areas and through engineered filter swales/turf parking areas for a minimum of 300 feet. The water from the club house and practice areas will have additional treatment in an existing irrigation pond and detention basin.
- 5) TP and TSS loads will meet the Commissions Standards. These loads are as follows;

	Total Phosphorus (lbs/year)		TSS (lbs/year)		
	Existing	Proposed	Existing	Proposed	
Practice Facility	8.9	7.0	1195	365	
Clubhouse Area	0.8	0.7	81	16	
Event Parking Lot	11.1	8.9	105	56	

6) Abstraction/volume controls necessary for the increase in impervious areas. Total increase in impervious areas will be 43,248 sq. ft. With the disconnection credits (75 feet for sheet flows or 300 feet for channel flows) the actual impervious area that needs abstraction is 7,925 sq. ft. All the other areas are routed over turf, filter swales or overland at least 300 feet before entering any water body or wetland. This allows these impervious areas to be considered disconnected and subtracted from our abstraction

Windsong Farm Golf Club Parking Lot and Practice Facility Improvements 2018-13, Independence October 5, 2018

- requirements. Actual filtration volumes created by permeable turf, filter swales and other engineered soil areas will be 6,972 cubic feet. 725 cubic feet of storage is required.
- 7) No floodplains or wetlands will be impacted by this site plan.
- 8) Grading and Erosion Controls; Silt fence, natural buffer areas and other construction BMP's are specified for the erosion and sediment controls during construction. These practices meet the Commission's erosion control requirements.

Recommendation: Approval.


Note: Staff recommends the applicant consider installing 2 grassed waterways in the cropland area north of the overflow parking (locations and typical cross section attached). If desired, agriculture BMP cost share is available for these waterways.


Hennepin County Department of Environmental Services Advisor to the Commission


James C. Kujawa,


Water Quality Specialist

October 15, 2018
Date









Grassed Waterway

Grassed waterways are constructed graded channels that are seeded to grass or other suitable vegetation. The vegetation slows the water and the grassed waterway conveys the water to a stable outlet at a non-erosive velocity.

Grass or permanent vegetation established in waterways protects the soil from concentrated flows. Grassed waterways significantly reduce gully erosion.

A natural drainage way is graded and shaped to form a smooth, bowl-shaped channel. This area is seeded to sod-forming grasses. Runoff water that flows down the drainage way flows across the grass rather than tearing away soil and forming a larger gully. An outlet is often installed at the base of the drainage way to stabilize the waterway and prevent a new gully from forming.

Grass cover protects the drainage way from gully erosion. Vegetation may act as a filter, absorbing some of the chemicals and nutrients in runoff water.

Vegetation provides cover for small birds and animals.

The expected life span of a waterway is 10 to 20 years. It is Highly determined by the amount of sediment that the grass in The waterway traps. Eventually the cropland at the edge of the grass And the waterway itself will need to be re-excavated to allow for the water to flow into and down the waterway. If upland erosion is not controlled, the lifespan of the waterway is greatly reduced.





MEMORANDUM

TO: Pioneer-Sarah Creek Watershed Management Commission

FROM: James Kujawa and Kirsten Barta, Hennepin County Dept. of Environment and Energy

DATE: October 11, 2018
SUBJECT: Staff Report

- 1. 2016-05 Proto Labs Parking Lot Expansion, Maple Plain. The Commission approved this project contingent upon three conditions. One condition remains open receipt of an Operation and Maintenance agreement on the biofiltration basin per Staff findings dated September 6, 2016. The agreement has been signed but remains to be recorded on the property title.
- 2. 2017-03 Equestrian Facility (Bel Farms) Independence. This is a 16.5 acre rural residential parcel located approximately 500 feet north of the intersection of CR6 and Nelson Road. The owner is proposing to construct a new garage/apartment, horse stall barn, indoor arena, outdoor arena, six grass and four sand paddocks for horses. Because this project disturbs greater than 1.0 acre and creates 3.1 acres of additional impervious area, it triggers the Commission's review for Rules D and E. Staff provided grading and erosion control approval contingent upon (1) The applicant assuming the risk and responsibility for any changes to the site plans necessary for final Commission approval and (2) The City of Independence approving a grading permit. In September 2017 the Commission approved the Stormwater Management Plan contingent upon receipt of an approved long-term pond/basin operation and maintenance plan between the landowner and City, to be recorded on the land title. No new information has been received since that time.
- 3. 2017-04 Windsong Farm Golf Club Practice Facility, Independence. This site is north of CR6 and the entrance to the current Windsong Golf Course. The total area owned by Windsong Farm Golf Club north of CR6 is 126 acres. This project will impact the three easterly parcels (36 acres) of their property. The applicant proposes to construct a new practice facility on a portion of these three parcels. Actual grading/disturbance will be 13.4 acres. New impervious areas will be 0.7 acres. The east shore of Fox Lake (DNR 925W) is the west border of the parcels being impacted. The Commission Rules that apply to this work include Rules D, E, F, and I. Staff recommended approval contingent upon: (1) Specific turf establishment timing requirements being outlined in the SWPPP or Site Plan, (2) Floodplain and Wetland/buffer easements being established over said features on the three parcels where this project is located, and (3) The locations and signage standards for the wetland buffer monumentation being provided to the Commission for review and approval. The Commission approved this project per Staff's recommendations. Item 1 has been addressed adequately, but Staff are still awaiting word on items 2 and 3. This project never proceeded. A new project was submitted revising the original plan and enlarging its scope. Based on the revised plan submittal, project 2017-04 will be removed from the report and project 2018-13 will be started in its place.
- 4. 2017-05 Ostberg Equestrian Facility, Independence. This is a 40-acre agriculture parcel located just southwest of the intersections of CSAH 6 and Game Farm Road. The owner is proposing to construct a new home, two garages, a horse stall barn, indoor arena, outdoor ring, eight horse paddocks and an access drive off of CSAH 6. The project will disturb 7 acres during construction and create 1.69 acres of new impervious areas. Because this project disturbs more than 1.0 acre and creates 1.7 acres of additional impervious area, this triggers the Commission's review for Rules D and E. There are also two wetlands that have been delineated on this site, so the Commission wetland buffer requirements (Rule I) are triggered. The project received grading and erosion control approval by Staff in October 2017 pending final Commission approvals. The project was approved by the Commission at their November 2017 meeting contingent upon receipt of an approved long-term pond/basin operation and maintenance plan between the landowner and the City, said plan to be recorded on the land title. This information has not been received as of this report.
- **2018-01 Salem Lane Reconstruction Project, Greenfield.** Salem Lane work must be reviewed for compliance with Rules E and F. A stormwater quality review is not necessary because the site disturbance is less than 1.0 acre and less than 0.5 acres of new impervious area. At the January 2018 meeting, this item was approved per Staff's recommendations. The only remaining item is Staff approval of the erosion and sediment control plans. These have not been submitted as of this report.

RULE G - WETLAND ALTERATION

Rule H – Bridge and Culvert Crossings

- **2018-02W Warren DaLuge Wetland Violation, Greenfield.** Staff met with DaLuge and came to an agreement for him to voluntarily remove any fill placed in the wetland on his farmstead by December 1, 2017.As of February 8 the work had not started. Staff requested a restoration order be issued for compliance by June 15. The order was sent by certified mail. Staff has stopped in on the site four or five times since the June 15th deadline. They have been actively moving dirt out of the wetland, but are only about 3/4 of the way done to date. As long as they continue to work on it, Staff will continue to monitor their progress and update the Commission.
- **7. 2018-07W 810 Copeland Road, Independence.** The City of Independence issued a notice last fall for this landowner to remove manure fill from Fox Lake. It has not been accomplished to date. The DNR and MPCA were contacted by PSC staff about this violation on May 30, 2018. The MN DNR issued a Resource Protection Order to the landowner on May 31, 2018. DNR Hydrologist Jason Spiegel and MPCA Feedlot Inspections Officer Walter Jordan were also contacted by PSC staff and visited the site. They are coordinating their efforts to have this material removed. The DNR surveyed the site and issued a restoration order giving them until September 30, 2018 to remove the material. This site has been restored and certified as complete by the DNR. This item will be removed from the report.
- **8. 2018-010 Chippewa Estates, Loretto.** This is a 1.54-acre parcel located in the far northeast corner of Loretto on Chippewa Road. The project is proposing to subdivide the lot into four single family residential lots and triggers the Commission's review for Rules D and E. The applicant has requested administrative approval from Staff to begin grading the site. Staff provided this approval contingent upon the City of Loretto issuing a grading permit and that the applicant understands they assume all risks associated with changes that may be necessary for final Commission approvals. At their August 16, 2018 meeting, the Commission approved Staff findings with three conditions regarding the operations and maintenance plan, sequencing, and retrofitting of the pond.

It is Staff's understanding that the City chose not to expand their existing regional pond to accommodate this site's stormwater, so the back and side yard filter system will be installed per the site plans. With this being the case, the only remaining item necessary for final approval is the Operation and Maintenance agreement on the stormwater system. If the City chooses not to maintain the filter system, the applicant must provide an operation and maintenance plan that is acceptable to the City and the Commission and must be recorded on the title to the property.

- 9. 2018-011W Hilary Driveway Access Wetland Replacement Plan, Greenfield.* This replacement plan corresponds to the Town Hall Drive Wetland Delineation (2018-09W) Two wetlands were identified, delineated and surveyed on the property with that delineation. This plan is for impacting and replacing 3,968 SF of wetland to install an access driveway into this lot. 2:1 replacement ratio mitigation is proposed. 1:1 credits from the Ball Wetland Bank (account 1546) in Greenfield and 1:1 credits from the Stamer Wetland Bank (account 1542) in Stearns County. The project application has been noticed per WCA requirements. A Technical Evaluation Panel (TEP) meeting on the sequencing analysis was held August 23, 2018. The TEP requested more information on the sequencing analysis before they could make their final recommendations. Based on additional information received on October 5, the TEP recommends that the sequencing analysis is adequate and that the Commission approve the wetland replacement plan Staff recommends approval of this wetland replacement plan.
- **2018-012W 7770 Woodland Trail, Greenfield.** This is a 41.5-acre parcel inspected on June 21, 2018 for the presence and extent of wetlands by Kjolhaug Environmental Services. It is located in Section 16, Township 119 North, Range 24 West, Hennepin County PID#: 1611924340002. Three wetlands were identified, delineated and surveyed on the property. Staff has visited the site and reviewed the report. The delineation was found to be accurate and has been approved per WCA requirements. This item will be removed from the report.
- **2018-013** Windsong Farm Golf Club Parking Lot and Practice Facility Improvements, Independence. This project will take place on the golf course property on both sides of CR 6. They propose to reconstruct their existing practice facility and clubhouse service access road, reconstruct their existing main parking lot and construct a new event overflow parking lot. Commission Rules that apply to this work will include Rules D and E. A recommendation will be provided to the Commission at their meeting.
- **12. 2018-014 Verizon Tower, Independence.** Verizon Wireless is proposing to build a 120-foot cell tower and a 12x30 foot equipment building on the south side of Highway 12, just west of Mobile Marine (PID

RULE D - STORMWATER MANAGEMENT

Rule E - Erosion and Sediment Control

Rule F-FLOODPLAIN ALTERATION

Language in red indicates current updates

Rule I — Buffers

* indicates enclosure

2

RULE G - WETLAND ALTERATION

Rule H - Bridge and Culvert Crossings

2211824440001). There is floodplain located on this property and the project is considered commercial. The Commission rules require review and approval of the grading and erosion control site plans. Disturbance and grading on this project will be less than 1 acre. Approximately 6,500 SF (0.15 acre) of new impervious area will be created. The disturbance and new impervious area do not trigger the thresholds for the Commission's review of stormwater management for this site. Staff will administratively approve this project.

13. 2018-015W Kettering Creek Wetland Delineation, Greenfield. This is two parcels with approximately 21 total acres (parcel numbers: 2811924320037 and 2811924320038). The western portion of the site is deciduous forest and the eastern side is a fallow field with wetlands. The eastern side was mass graded sometime between 2003 and 2006 as part of the Greenfield Business and Industrial Park. Westwood delineated two wetlands (W1 and W2) and one watercourse (WC1) on these parcels. Staff has visited the site and reviewed the delineation report and finds the delineation to be accurate. The public comment period on this delineation report expires on October 15, 2018. If no comments are received, it will be approved and noticed per WCA requirements.

LOCAL WATER PLANS

Per the amended MN Rule 8410.0105, subp. 9, and 8410.0160, subp. 6, Local Water Plans must be prepared by metropolitan cities and towns and must become part of their local comprehensive plans. They must be revised essentially once every ten years in alignment with the local comprehensive plan schedule. A municipality has two years prior to its local comprehensive plan being due to adopt its local water plan. The next local comprehensive plans are due December 31, 2018; thus all cities and towns in the seven-country metropolitan area must complete and adopt their local plans between January 1, 2017 and December 31, 2018.

Local plans from the cities of Loretto and Medina were approved in 2017.

Minnetrista's Local Plan was reviewed and comments were provided to the city in July. Updated stormwater management plans were received in September. Staff reviewed the updates and recommends the Commission approve the City of Minnetrista's Final Comprehensive Surface Water Management Plan dated September 2018. See memo in this month's packet.

Greenfield's Local Plan comments were forwarded to the City in August 2018 for their consideration in their final plan. No updates to the plan have been received to date.

GRANT OPPORTUNITIES

MPCA put out an RFP for section 319 funding (pass through from US EPA) to implement watershed wide impairment reductions. Hennepin Staff put in an application on behalf of the watershed, but Pioneer Sarah Creek was not selected for the final round of consideration this year. MPCA feedback indicates there were two reasons for this: 1. Lack of general idea how much it would cost to clean up the entire watershed (staff will work on producing this for the next round of applications), and 2. Because the state is not confident the watershed itself would be willing to invest in this project. Pioneer Sarah Creek does not have a strong track record of spending or allocating funds for larger projects so MPCA was not comfortable entering into a 16 year pilot program that involves spending a significant amount of money at this time.

Hennepin will work together with TRPD staff to come up with some kind of ballpark monetary amount for the next round of applications – there will be three more years to apply.

Z:\Pioneer-SarahCreek\TechMemos\Tech Memos 2018\October Tech Memo_V2.docx

Rule D - Stormwater Management

Rule E - Erosion and Sediment Control

RULE F - FLOODPLAIN ALTERATION

Language in red indicates current updates

RULE G - WETLAND ALTERATION
RULE H — BRIDGE AND CULVERT CROSSINGS

RULE I - BUFFERS



ADMINISTRATIVE OFFICE: 3235 Fernbrook Lane N • Plymouth, MN 55447

763.553.1144 • Fax: 763.553.9326

TECHNICAL OFFICE: 701 Fourth Street South, Suite 700, Minneapolis, MN 55415-1600

612.348.7338 • Fax: 612-348-8532

DATE: OCTOBER 15, 2018

TO KIRSTEN BARTA, RURAL CONSERVATIONIST, HENNEPIN COUNTY

DEPARTMENT OF ENVIRONMENT AND ENERGY,

FROM: JIM KUJAWA

RE: PIONEER-SARAH CREEK WATERSHED METRICS DATA REQUEST

Below is the information you requested. If you would like more detailed information, please visit our web site at the following link; http://www.pioneersarahcreek.org/annual-reports.html. This link has the PSCWMC annual reports between 2003 and 2017.

The following information is from our 2017 annual report. We reviewed 7 site plans for our member communities of Greenfield, Independence, Minnetrista, Medina, Maple Plain and Loretto. Please let me know if you have any questions.

- 1. Numbers on TSS reductions (in tons) and any Phosphorus or nutrient reductions you have (in pounds)
- 2. How many projects you have completed (both capital and cost share)

Baker Regional Park, gully control project was approved for design with construction expected in 2018-2019. The most cost-effective approach to stabilize the channel is to install a series of rock grade control structures throughout the main ravine and two tributaiy ravines to control the channel grade as well as line the entire channel with combination of rounded field stone and angular rip-rap up to the expected 10-year flood elevation. Average annual phosphorus loads to Lake Independence would be reduced by an estimated 134 pounds, at a cost per pound of phosphorus load reduction of less than \$130/16. based on a project life of 30 years. This reduction in annual phosphorus load would accomplish 15% of the total watershed phosphorus load reduction called for in the TMDL.

Greenfield identified a non-CIP project at Central Park and the Commission cost-shared in this project with multiple benefits. This project will install a diversion swale and stormwater pond to control surface water from the City's Central Park from running into cropland below the park. The project will capture nearly all runoff from City Park and reduce phosphorus loads by 6 lbs. per year into the Dance Hall Creek Watershed and Lake Sarah. As a component to the stormwater pond work the City of Greenfield proposes to install native pollinator and vegetation plantings within the project area to help stabilize, improve and diversify natural resource outcomes of the project.

3. A few stories or neat project descriptions and pictures!

4. Any challenges you are facing and why

Challenges are working in the rural area and getting 'buy-in' from these landowners to install long term sustainable conservation practices that will reduce TMDL/WRAPS impairments in our watershed. Landowner skepticism with government and/or that there is a problem.

5. Your current highest priority issues to tackle in your watershed

See #4, specifically in the rural areas of the Ardmore, Independence, and Dance Hall Creek subwatershed assessments

6. Any additional quantitative water quality metrics you have – for example de-listing of impaired waters, pounds of trash removed, residents engaged or educated, pounds of carp removed

The WRAPS study was approved by the MPCA on July 26, 2017. The EPA approved the Pioneer-Sarah Creek TMDL on September 29, 2017. Both reports are available on the Commission's website, http://www.pioneersarahcreek.org/wraps.html, and the MPCA website at https://www.pca.state.mn.us/water/tmdl/pioneer-sarah-creek-watershed-restoration-and-protection-strategy-tmdl-project.

7. Statistics on what types of projects you are doing – erosion control, carp removals, rain gardens, stream restorations, alum treatments, that type of thing

Commission staff assisted approximately 25 landowners/agency/developer contacts with wetland-related questions. In Greenfield, Loretto and Maple Plain, they reviewed five wetland boundary/type applications; three wetland no-loss/exemptions and one wetland sequencing analysis. No wetlands were impacted in the above mentioned communities.

Four WCA violations were investigated and resolved; two others were determined to not be WCA/Commission violations. The Commission participated in five Technical Evaluation Panels (TEPs) throughout the watershed.

Partner with Three Rivers Park District (TRPD) to conduct bi-weekly water quality monitoring of "sentinel lakes" – Independence, Sarah, and Little Long, along with both basins of Whaletail Lake. Ardmore, Half Moon, Hafften and Spurzem Lakes were also included in the 2017 lake monitoring program.

2017 was the final year of planned whole-lake CLP treatments for Lake Sarah. The Commission's cost share was \$8,823.

8. Future priorities

Expand our education outreach programs

Utilize our BWSR watershed wide grant money for three projects identified in the Lake Ardmore Subwatershed Assessment. 1) Project SS1, Stream Stabilization. Stabilize 70 feet of stream bank erosion in channel between Lakes Ardmore and Independence. 2) Project SR1, Shoreline Restoration. Stabilize 160 feet of shoreline at boat launch. 3) Project PD3, Pond Excavation, and Enlarge existing stormwater pond to provide additional treatment for urban runoff. These three projects will reduce nutrient loads into the area lakes by 3.3 lbs/year of phosphorus and approximately 6,000 lbs/year of total suspended solids.

9. Anything else you especially want to highlight

The Commission's Facebook page was introduced in 2017. Content is posted for free and includes links to the Commission and other partner websites. There were 36 posts; largest reach was 194 people and 21 engagements.

JCK

Technical Memo



To: Justin Berndt, Project Manager, US Army Corps of Engineers

From: Lucius Jonett, Wenck Associates, Inc.

Copy: Brian Vlach, Senior Water Resources Manager, Three Rivers Park District

Date: September 24, 2018

Subject: Baker Ravine Stabilization – Basis of Design

Lake Independence is a recreational lake impaired for excess nutrients. In 2007, a TMDL was approved for Lake Independence requiring that the phosphorous load be reduced to an in-lake growing season mean of 36 ug/l for total phosphorus. The TMDL set a target of reducing the TP loading from the watershed by 1,081 lbs./yr., a 45% reduction from the baseline condition. The cities with land that drain to the lake each have an obligation under the TMDL to reduce phosphorus loading to the lake; Independence by 535 pounds per year, Medina by 284 pounds per year, and Loretto by 53 pounds per year. The City of Maple Plain was not assigned a TP load reduction under the TMDL.

In order to meet their TMDL requirements, the City of Independence hired the Anoka Conservation District (ACD) to complete the Lake Sarah and Lake Independence Stormwater Retrofit Analysis. This report was completed in 2014 and identifies several eroding ravines as sources of pollutants to Lake Sarah and Lake Independence. One of the identified ravines (GS-50 or Baker Ravine) discharges to Lake Independence and is located on Three Rivers Park District (TRPD) property at Baker Park Reserve. The study identified GS-50 as a significant source of sediment and phosphorus discharge (300 tons of sediment and 277 lbs. of phosphorous annually) to the lake and was given a high priority for stabilization, though the analysis stopped short of recommending specific remedial actions because the ravine and much if its watershed were outside the City of Independence.

Three Rivers Park District (TRPD), City of Independence, City of Medina, and the Pioneer-Sarah Creek Watershed Management Commission (PSCWMC) were interested in further investigating approaches to reducing the pollutant loading exported to Lake Independence from the ravine. TRPD hired Wenck in 2016 to complete a Ravine and Subwatershed Assessment to prescribe appropriate stormwater management practices in the watershed draining to the ravine as well as stabilizing the ravine itself. One of the key findings from the assessment work was that the most cost-effective project to decrease phosphorus loading to Lake Independence from the project area is to stabilize the main ravine channel. A further reduction in phosphorus loading would be achieved by stabilizing two secondary drainage channels that are tributary to the main ravine.

The recommended approach for stabilization is to install a series of riprap swales and control structures throughout the ravine to control the channel grade as well as line a portion of the channel with vegetated riprap up to the water elevation expected for a 10-year discharge event. Estimated 30-year life cycle costs for the stabilization of the main ravine channel is \$376,500 and two tributary channels is \$94,500. The estimated annual TP

Justin Berndt Project Manager U.S. Army Corp of Engineers September 24, 2018



load reduction from the main channel is 112 pounds and from the two tributary channels is another 22 pounds. The total estimated TP load reduction of 134 pounds accounts for a 12% load reduction from the watershed as required in the TMDL. The lifecycle costs per pound of TP is \$112 for the main channel and \$143 for the two tributary channels.

TRPD and the Pioneer-Sarah Creek Watershed Management Commission (PSCWMC) used the Ravine and Subwatershed Assessment to apply for and were selected for a BWSR Clean Water Fund grant to help fund the project. Other funding partners include a Hennepin County opportunity grant, PSCWMC, TRPD, City of Independence, City of Medina and the Lake Independence Citizens Association. The following table summarizes the funding sources and amounts:

Funding Source		Funding Amount	
BWSR Clean Water Fund	\$	416,000	
Hennepin County Opportunity Grant		59,500	
Pioneer-Sarah Creek Watershed Management Commission	\$	10,500	
City of Independence		10,500	
City of Medina		10,500	
Three Rivers Park District		10,500	
Lake Independence Citizens Association		2,500	
Total Funding	\$	520,000	

Design Considerations

Wenck progressed through final design of the ravine stabilization balancing several goals and priorities to find the best solution that met as many of them as possible while still meeting the requirement of reducing sediment and nutrient load to Lake Independence. These requirements include:

- Reduce long-term maintenance. This project is a "once in a life time" type project due to the construction costs and site access to and through the ravine. It has to be completed effectively and be long-lasting. Once the stabilization practices are installed, getting through the ravine in the future will require driving over the installed practices. If a stabilization feature were to fail in the middle, getting to it would be destructive and require repair to the other features that are driven over.
- Minimize the amount of tree removal to only what is necessary for construction access as governed by Three Rivers Park District ordinances. All TRPD properties must maintain a high percentage of natural vegetation communities, which only allows a fixed percentage of the property to be developed. Major tree removal would change the existing plant community and would constrain any future development activities at the Baker Park Reserve so only the number of trees needed for construction and site access is allowed. All tree removals for access have been strategically proposed on the south sides of the side ravines to maintain the maximum amount of buffer between the ravines and the campground on the north side of the side ravines.
- Use bioengineering practices to the extent possible. Aesthetically, TRPD wants the ravine
 to look as natural as possible. Wenck proposes to start with the softest practices
 possible when design ravine stabilization projects; from doing nothing, to resloping and
 revegetating, using woody material to armor toe of slopes, to using vegetated riprap to

Justin Berndt Project Manager U.S. Army Corp of Engineers September 24, 2018



armor toe of slopes. There is no intent to riprap the entire ravine, only what is needed for the long-term success of the project. The same thought process has been applied to Baker Ravine and as a result several areas will have no practices applied where they are not necessary. This assessment method also allows for the avoidance of sensitive resources, such as the delineated wetland within the channel. Revegetation efforts are going to be very limited since the tree removal is also limited. All disturbed areas, vegetated riprap areas, and a buffer along the creek will be seeded with native seed mix to aim for establishment of an understory community from the additional sunlight that will reach the forest floor after the selective tree removal is completed. Woody material as an in-channel practice has also been ruled out based on life expectancy. The best long-term solution is to use angular granite riprap which will outlast woody materials that have an expected life of 15-20 years. Riprap will be installed by shaping slopes and covering the riprap with soil and seeding it to camouflage the practice as much as possible and allow for some native vegetation to establish over the armoring. Soil will not be placed below the 10-year or Normal Water Level elevations as it will likely wash away before any vegetation could establish.

 Minimize impact to existing water and natural resources like wetlands, sensitive plant communities, etc. During the site topography survey, Wenck identified and marked trees and delineated one wetland. The project was designed around the wetland, a 15' nowork buffer added to the wetland boundary and all construction access routed around the wetland so that there would be zero impact.

Wenck went through preliminary design of the project, had a site meeting with TRPD to review and edit the preliminary design, and has finalized the ravine stabilization project design accomplishing the above objectives.

Permitting & Coordination

As part of the preliminary design, we reached out to the regulatory agencies that might have jurisdiction and want to review the project including, Pioneer-Sarah Creek Watershed Management Commission, MN DNR and the US Army Corps of Engineers. The MN DNR has determined that they do not need to review this project.

Prior to submitting a Joint Application and impact figure to the Corps, we requested an onsite meeting with staff to review the site, the project and discuss the best permitting route and Corps jurisdiction of the resource. The ravine water level is driven largely by stormwater and consistently contains no water throughout portions of its reach, making it challenging to identify the extent of regulatory water resource present. During the site visit, the extent of Corps jurisdiction was determined, and the Normal Water Level was established. We are requesting approval to perform this work under Nationwide Permit 13, Bank Stabilization, with a request for a waiver to the 500-linear foot threshold. This project aims to perform the bank stabilization activities as necessary for erosion control after careful thought and consideration towards the level of armoring. We do not anticipate that the discharge will result in any more than minimal adverse environmental effects and have designed the project to provide a significant ecological benefit to downstream water resources. The project does not propose more than an average of one cubic yard per running foot of stabilization practices and no discharges in special aquatic sites (wetland) will occur.

Justin Berndt Project Manager U.S. Army Corp of Engineers September 24, 2018



Conclusion

Information gathered and discussed during the site visit with the Corps was used to delineate a Normal Water Level within the ravine the following day and is shown on the plans to describe the physical extent of Corps jurisdiction. We appreciate the Corp staff time in meeting onsite and respectfully submit our application for your review on the Baker Ravine stabilization project.



















BAKER RAVINE STABILIZATION

Presented by Lucius Jonett, PLA




WHY





South Side Channel Looking Downstream



Existing Gabion Basket Grade Control Structures





Looking Upstream, South Side Channel from Main Ravine

Outside Bend Erosion from Stormwater Flow Through the Ravine Channel



Outside Bend Erosion from Stormwater Flow Through the Ravine Channel



Looking Upstream, North Side Channel from Main Ravine




North Side Channel Looking Downstream



Main Ravine Channel Viewed from North Side Channel



Without open canopy and sunlight, ground cover vegetation will not establish to stabilize banks.



Pink flags of delineated wetland area. Lake Independence visible downstream.

LAKE INDEPENDENCE


A recreational lake impaired for excess nutrients

- 2007 TMDL approved for Lake Independence requiring that the phosphorous load be reduced
- 2014 City of Independence hired the Anoka Conservation District (ACD) to complete the Lake Sarah and Lake Independence Stormwater Retrofit Analysis
- 2016 Three Rivers Park District (TRPD) hired Wenck to complete a Ravine and Subwatershed Assessment
- **BWSR Clean Water Fund Grant** Other funding partners are included in the following table:


Funding Source		Fur	nding Amount
BWSR Clean Water Fund		\$	416,000
Hennepin County Opportunity Grant		\$	59,500
PSCWMC		\$	10,500
City of Independence		\$	10,500
City of Medina		\$	10,500
Three Rivers Park District		\$	10,500
Lake Independence Citizens Association		\$	2,500
	Total Funding	\$	520,000

POLLUTANT REMOVAL ESTIMATES

- The estimated annual TP load reduction from the main channel is 112 pounds and from the two tributary channels is another 22 pounds.
- The total estimated TP load reduction of 134 pounds accounts for 15% of the watershed and 12% of the total phosphorus (watershed + internal) removal required to meet water quality goals in the TMDL.
- The lifecycle costs per pound of TP is \$130 per pound.



DESIGN







Before Tree Clearing





More Tree Clearing

Construction



Construction



Construction





Vegetation

3-Months After Vegetation





9-Months After Vegetation

16-Months After Vegetation


SIMILAR PROJECT – GLEN CREEK





SIMILAR PROJECT – GLEN CREEK





Tree Clearing

Construction

SIMILAR PROJECT – GLEN CREEK





Construction





Construction





Revegetation

13-Months After Revegetation





13-Months After Revegetation

24-Months After Revegetation



24-Months After Revegetation

CONSTRUCTION PLANS FOR BAKER RAVINE STABILIZATION PREPARED FOR PIONEER-SARAH CREEK WATERSHED MANAGEMENT COMMISSION AUGUST 2018



PROJECT VICINITY MAP

INDEX OF SHEETS:

G-101 - TITLE SHEET & INDEX

G-102 - LEGEND AND NOTES

C-100 - SITE ACCESS PLAN

C-101 - EXISTING CONDITIONS & REMOVALS

C-111 - PLAN AND PROFILE 0+00 TO 7+50

C-112 - PLAN AND PROFILE 7+50 TO 16+43

C-113 - PLAN AND PROFILE 20+00 TO 23+71

AND 30+00 TO 32+40

C-201 - SWPPP

C-202 - EROSION CONTROL PLAN

C-801 - DETAILS C-802 - DETAILS

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CALLING FOR LOCATIONS OF ALL EXISTING UTILITIES. THE COOPERATE WITH ALL UTILITY COMPANES IN MAINTAINING THEIR SERVICE AND/OR RELOCATION OF LINES.

THE LOCATIONS OF ALL UNDERGROUND WIRES, CABLES, CONDUTS, PIPES, MARROLES, VALVES OR OTHER BURIED STRUCTURES BEFORE DIGGING. THE CONTRACTOR SHALL REPAIR OR REPLACE THE ABOVE WHEN DAMAGED DURIS CONSTRUCTION AT NO COST TO BIE CAMBIR.

GOPHER STATE ONE CALL

G-101

GENERAL NOTES:

- GENERAL NOTES:

 1. DISTING CONDITIONS HAVE BEEN PROVIDED BY A COMBINATION OF HISTORIC PLANS FROM THE CITY, SUMPLY INFORMATION FROM A SITE VISIT BY WEIGHT STAFF AND LUDAR, DISTING FRANKES HAVE NOT BE EDUCT TO THERE LOCATIONS. THE CONTRIBATION IS RESPONDED FOR YEAR HAVE CONDITIONS OF THE SITE AND BUILD KNOTH THE SITE AND SITE OF THE SITE OF THE

- EXISTING PAVEMENT, CURBING, AND STRIPING SHALL BE REPLACED BY THE CONTRACTOR, TO THE OWNERS SATISFACTION, AT NO ADDITIONAL COST TO THE OWNER.

REMOVAL NOTES:

FEATURES NOT SPECIFICALLY IDENTIFIED ON PLAN FOR SALVAGE OR REMOVAL THAT CONFLICT WITH CONSTRUCTION ARE TO BE REVIEWED WITH ENGINEER.

DEWATERING NOTES:

- NO BID ITEM HAS BEEN PROVIDED FOR DEWATERING AS ALL DEWATERING WORK NECESSARY FOR CONSTRUCTION MIL BE CONSIDERED MICEDENTIAL.

 PROVIDE STATEMENT OF THE PROVIDED AT ALL DESCHARGE PROVIDED AT A FOREST OF THE PROVIDED PRIOR TO STATEMEN ANY CONSTRUCTION ACTIVITIES.
- THE CONTRACTOR MUST DISCHARGE TURBO OR SEDMENT-LADED WATER RELATED TO DEMANERING OR BASIN DRAWING C.C. PUMPED DISCHARGES, TREMCHIOTH CUTS FOR DRAWARD, TO A TEMPORARY OR PORMANENT SEDMENTATION BESIN ON THE PROJECT STE UNILSS INTEREDISE. THE CONTRACTOR MAY DISCHARGE FROM THE TEMPORARY OR MY PERMANENT SEDMENTATION BESINS TO THE SIGNAL BATTOR, IT THE BASIN MATTER WITH THE BASIN MATTER THE BASIN MATTER WAS THE BASIN MATTER THE BASIN MATTER THE BASIN AND THAT MUSINSOC COMMITTORS (SEE MAN 1982-5 7950.2012, 1987-847). BY THE SESSION AND THAT MUSINSOC COMMITTERS OF THE DISCHARGE TO A MY SECRETARY OF THE SECTION OF THE PROPERTY OF THE SECTION OF THE TRACTOR WITH THE PROPERTY OF THE SECTION OF THE TRACTOR OF THE PROPERTY OF THE SECTION OF THE PROPERTY OF THE CONTRACTOR MUST OF THE PROPERTY OF THE PROPERTY OF THE CONTRACTOR OF THE THE PROPERTY OF THE PROPERTY OF THE CONTRACTOR OF THE PROPERTY OF THE PROPERTY OF THE CONTRACTOR OF THE PROPERTY OF THE OL-MATER SEPARATION ON SUITABLE PLITARION ORDING LEC. CONTRIDER FILTERS,
 ASSORBENTS AND PRIOR TO DESCRIPTION OF THE PLE CONTRIDER FILTERS,
 ASSORBENTS AND PRIOR TO DESCRIPTION OF THE PLE CONTRIDER MASS INSURED.
 SEPARATION OF THE ASSOCIATION OF THE PLE CONTRIDER OF THE PLE CONTRIDER OF THE ASSOCIATION OF THE ASSOCIATI
- ANY-RISE MAPACT TO THE WETLAND. FOR THE SCHWASH WATER, THE CONTRACTOR MUST FITE CONTRACTOR IS USING FILTERS WITH BACKWASH WATER, THE CONTRACTOR MUST HULL THE BECKNING HATER AWAY FOR DISPOSAL, RETURN THE BECKNING FOR THE TEXT PROCESS, OR INTO THE BECKNING OF THE TEXT PROCESS. OR TO CAUSE ENGIGINE THE CONTRACTOR MAY DOCKNING BACKWASH WATER TO THE SWITHART SERVER IF PRIMISSON IS CRAVITED BY DOCKNING BACKWASH WATER TO THE SWITHART SERVER IF PRIMISSON IS CRAVITED BY THE TEXT WATER AND THE SWITHART SERVER IS PRIMISSON IN CRAVITED BY THE TEXT WATER AND THE SWITHART SERVER IS PRIMED AND THE PRIME AND CLUEN THE PRINCIPLO.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CALLING FOR LOCATIONS OF ALL EXISTING UTILITIES. THEY SHALL COOPERATE WITH ALL UTILITY COMPANIES IN MAINTAINING THEIR SERVICE AND/OR RELOCATION OF LINES.

THE CONTRACTOR SHALL CONTACT GOPHER STATE ONE CALL AT 651-454-0002 AT LEAST 48 HOURS IN ADVANCE FOR THE LOCATIONS OF ALL UNDERGROUND WIRES, CABLES, CONDUITS, PIPES, MANHOLES, VALVES OR OTHER BURIED STRUCTURES BEFORE DIGGING. THE CONTRACTOR SHALL REPAIR OR REPLACE THE ABOVE WHEN DAMAGED DURING CONSTRUCTION AT NO COST TO THE OWNER.

GOPHER STATE ONE CALL

TWN CITY AREA: 651-454-0002 TOLL FREE 1-800-252-1166

GOVERNING SPECIFICATIONS:

- THE MINNESOTA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION" 2016 EDITION & LATEST SUPPLEMENTS.

 OITY PROMERES ASSOCIATION OF MINNESOTA (CEAM) STANDARD UTILITIES SPECIFICATIONS (LATEST EDITION).

 OITY OF PLANDUIST CONSTRUCTION SPECIFICATIONS.

 ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS AND ORDINANCE WILL BE COMPLETED WITH IN THE CONSTRUCTION OF THIS PROJECT.

 OWNER OF WITH IN THE CONSTRUCTION OF THIS PROJECT.

 OFFICE OF WITH IN THE CONSTRUCTION OF THIS PROJECT.

 ONE OF THIS PROJECT.

TRAFFIC CONTROL NOTES:

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL CONSTRUCTION STACING, ON OR OFFSITE, AS NECESSARY TO COMPETE THE WORK AS SPECIFIED IN THE PROJECT DOCUMENTS, AS TAKING PAIN SHALL BE SUBJUNTED TO THE EMBORIZER FOR REVIEW AND APPROVAL PRIOR TO ANY CONSTRUCTION RELATED ACTIVITIES.
 CONTRICTORS SHALL BE RESPONSIBLE FOR ALL TRAFFIC CONTRIOL, ALL TRAFFIC CONTRIOL AND ANY CONTRICTOR SHALL CONFIDENT TO THE MAJOR. FOR ALL TRAFFIC CONTRIOL AND ANY CONTRICTOR SHALL BE RESPONSIBLE FOR ALL TRAFFIC CONTRIOL. ALL TRAFFIC CONTRIOL AND ANY CONTRIOL FOR THE MAJOR FOR THE CONTRIOL AND ANY CONTRIOL FOR THE MAJOR FOR THE CONTRIOL AND ANY CONTRIOL FOR THE MAJOR FOR T
- APPLICABLE PERMIT REQUIREMENTS.
 TRAFFIC CONTROL SHALL ALSO INCLUDE ALL NECESSARY SIGNAGE AND MARKINGS REQUIRED FOR THE BOARDWALK CLOSURE (SIMILAR TO SIDEWALK CLOSURE). THIS SHALL INCLUDE ADVANCED WARNING SIGNS AND NECESSARY FENORIC AND SIGNAGE TO PREVENT PEDESTRIANS FROM ACCESSING THE PROPOSED BOARDWALK CONNECTION AREA.

EROSION CONTROL NOTES:

- SEE SHEETS C-201 AND C-202 FOR EROSION AND SEDMENT CONTROL MEASURES. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED GEPENDING ON SITE CONDITIONS DURING CONSTRUCTION. COORDINATE WITH ENORMER. ALL EROSION CONTROL DEVICES TO BE INSTALLED PRIOR TO COMMENCEMENT OF WORK,
- ALL BEDSON CONTROL DEVICES TO BE A PROJECTED PROPERTY OF COMMERCEMENT OF WORKSTAME OF WORKSTAME OF THE PROJECT, AND FROM UPON ESTABLISHMENT OF THAT STREAMED NOT BE PROMITED THAT STREAMED BY CONTROL ON THE CONTROL OF CONTROL OF CONTROL OF CONTROL OF CONTROL ON SHALL NOT BE REMOVED UNTIL AUTHORIZED OF CONTROL OF CONTROL

HORIZONTAL AND VERTICAL CONTROL:

- 1. THE HORIZONTAL CONTROL FOR THIS PLAN IS HENNEPIN COUNTY COORDINATE.

ABBREVIATIONS

WATERMAIN

EXISTING SYMBOLS/LINES LEGEND

STORM SEWER FLARED END SECTION STORM SEWER CATCH BASIN/MANHOLE HYDRANT

WATER MAIN ---- CONTOUR MINOR ----- CONTOUR MAJOR

----- PROPERTY LINE ----- ACCESS ROUTE BOUNDARY

- - EXISTING CHANNEL APPROXIMATE TREE LINE

- WETLAND BOUNDARY 0

> UTILITY POLE LIGHT POLE

SIGN

GUARD POST

PROPERTY IRON

PROPOSED SYMBOLS/LINES LEGEND

RIP RAP

STORM SEWER CATCH BASIN/MANHOLE

- TWO STAGE CHANNEL

CHANNEL CLEANOUT HITTHITHITHITH GRADED BANK

CONTOUR MINOR

HALLING SPOT ELEVATION

CONCRETE

EXISTING SENGE ---- PROPERTY LINE HIHITHIHIHIHIH GRADED BANK

======= BARE ROOT SHRUB PLANTING 2R3QJU08 0000000000

──── WATER EDGE RETAINING WALL ----- PROPOSED CHANNEL CENTERLINE

---- PROJECT AREA LIMITS -x-x-x-x-x-x- ROOTWAD WITH LOG TOE VEGETATED RIPRAP TOE

COIR TOE SINGLE LANE ACCESS PLOWED FOR WINTER PEDESTRIAN

ACTIVITIES BY THREE RIVER PARK DISTRICT ---- CONSTRUCTION AND STAGING ACESS TO BE PLOWED BY

REMOVAL SYMBOLS/LINES LEGEND

MISCELLANEOUS REMOVALS

EROSION CONTROL SYMBOLS/LINES LEGEND

OOOOO SEED MIX 34-262

HYDROMULCH AND MN SEED MIX 34-262

-0-0-0- FLOTATION SILT CURTAIN

---- BioROLL

WENCK 3


MANAGEMENT KER RAVINE STABILIZATION COUNTY RD 24 MAPLE PLAIN, MN 55359 INDEER-SARAH CREEK WATERSH COMMISSION
3235 FERNBROOK LANE N PLYMOUTH, MN 55447 8AK

PRELIMINARY


SJB XXXX


G-102






C-101







PROJECT INFORMATION

PROJECT NAME: BAKED DAVINE STABILIZATION PROJECT LOCATION: 3800 COUNTY RD 24, MAPLE PLAIN, MN PROJECT TYPE: STREAM BANK RESTORATION

TOTAL AREA DISTURBED BY CONSTRUCTION: ±1.5 ACRES. TOTAL SITE AREA: ±1.5 ACRES. ESTIMATED CONSTRUCTION DATES: FEBRUARY 2019 - JUNE 2019

CUMULATIVE IMPERVIOUS SURFACE/PERMANENT STORMWATER MANAGEMENT REQUIREMENTS THERE IS CURRENTLY ±0.0 ACRES OF EXISTING IMPERVIOUS SURFACE IN THE PROJECT AREA.

THE PROPOSED AREA OF IMPERVIOUS IS ±0.0 ACRES RESULTING IN A ±0.0 ACRE NET INCREASE IN IMPERVIOUS SURFACE.

THE SITE ULTIMATELY DRAINS TO LAKE INDEPENDENCE, WHICH IS LISTED AS AN IMPAIRED WATER FOR AQUATIC CONSUMPTION AND AQUATIC RECREATION. THERE ARE CURRENT EPA APPROVED TMOLS FOR THE WATERBODY FOR MERCURY IN FISH TISSUE AND NUTRIENTS.


THE CONSTRUCTION PLANS OUTLINE STABILIZATION PRACTICES INCLUDING RIPRAP, ROCK TOES, SEEDING, AND INSTALLATION OF EROSION CONTROL BLANKET FOR VEGETATIVE RE-ESTABLISHMENT.

PARTY RESPONSIBLE FOR LONG TERM OPERATION AND MAINTENANCE OF THE SITE (OWNER)

THREE RIVERS PARK DISTRICT CONTACT: XXXXXX CONTACT PHONE: (XXX) XXX-XX CONTACT EMAIL: XXXXXXXXXX

PARTY RESPONSIBLE FOR IMPLEMENTATION OF THE SWPPP (CONTRACTOR):

SOIL MAP



IN ACCORDANCE WITH PART III.A.2.A.I. OF THE GENERAL PERMIT AUTHORIZATION TO DISCHARGE STORMWATER ASSOCIATED WITH CONSTRUCTION ACTIVITY UNDER THE NPOES, THE PREPARER OF THIS DOCUMENT WAS TRAINED UNDER THE UNIVERSITY OF MINNESOTA EROSION AND SEDIMENT CONTROL CERTIFICATION PROGRAM. LOUIS SIGTERMANS! CERTIFICATION IN DESIGN OF SWPPP IS VALID THROUGH MAY 31, 2020

EROSION AND SEDIMENT CONTROL

PRIOR TO ANY SITE DISTURBANCE, AND AS REQUIRED AS CONSTRUCTION PROGRESSES, ANY PERMIT REQUIRED REOSION PREVENTION MEASURES AND THE SEDIMENT CONTROL DEVICES (BIOLOGY, FLOATING SITE CURTENI, NILET PROTECTION, SEDIMENT TRAPPIRASIN, EROSION CONTROL BLANKET) SHOWN ON THE CONSTRUCTION OF ANY PROPERTY.

ALL EXPOSED SOIL AREAS WITHIN THE CONSTRUCTION LIMITS WILL BE STABILIZED WITHIN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY (WILL NOT RESUME FOR A PERIOD PORTION OF THE SITE HAS TRIMPORABLEY (WILL NOT RESUME) FOR A PURIOD EXCEEDING 7 CALENDAR DAYS) OR PERMARENTLY CEASED. STABILIZATION WILL BE INITIATED IMMEDIATELY. EXPOSED SOIL AREAS MUST HAVE TEMPORARY EROSION PROTECTION (SLASH MULICH, EROSION CONTROL BLANKET, SEED) OR PERMANENT COVER YEAR ROUND.

CONTRACTOR SHALL IMPLEMENT APPROPRIATE CONSTRUCTION PHASING, VEGETATIVE BUFFER STRIPS, HORGONTAL SLOPE GRADING, AND OTHER VOCASTBUCTION PRACTICES THAT MINIMIZE EROSION WHEN PRACTICAL THE NORMAL WETTED PERMETER OF ANY TEMPORARY OR FERMANENT GRANAGE DITCH THAT DANSING WATER FROM A CONSTRUCTION SET, OR DIVERTS WATER AROUND A SITE, MINIST BE STABILIZED WITHIN 200 LINEAU, FEET FROM THE PROPERTY EDG. OF FROM THE GROWN OF DECKNORY OF ANY SUFFRACE WATER, STABILIZATION MUST BE COMPLETED WITHIN A HOURS OF CONNECTING TO A SUFFRACE WATER. STABILIZATION MUST BE COMPLETED WITHIN A HOURS OF CONNECTING TO A SUFFRACE WATER. PER COLITES MUST BE PROVIDED WITH EMPORARY OR PERMANENT ENERGY DISSIPATION WITHIN 24 HOURS OF CONNECTION TO A SURFACE WATER

SWIPPP IMPLEMENTATION, PHASING, AND SEQUENCE OF CONSTRUCTION

BMP AND EROSION CONTROL INSTALLATION SEQUENCE SHALL BE AS FOLLOWS:

- INSTALL PERIMETER CONTROL, FLOATING SILT CURTAIN, INLET
- PREPARE TEMPORARY STORAGE, ACCESS, PARKING, AND PHASING AREAS.
- AREAS.
 CONSTRUCT AND STABILIZE DIVERSIONS AND TEMPORARY SEDIMENT TRAP/BASIN IN THE LOCATION SHOWN ON THE PLANS.
- PERFORM CLEARING AND GRUBBING OF THE SITE, IF APPLICABLE, START CONSTRUCTION OF REPAIRS.
- NIART CONSTRUCTION OF REPAIRS
 PERFORM MASS GRADNE, RODGE GRADE TO ESTABLISH PROPOSED
 DRAINAGE PATTERNS.
 TEMPORARIES SEED WITH PURE LIVE SEED THROUGHOUT CONSTRUCTION
 DISTURBED AREAS THAT WILL BE INACTIVE FOR SEVEN (7 DAYS), OR MORE
 AS REQUIRED OF HYDGS PERMIT.

SEDIMENT CONTROL PRACTICES MUST MINIMIZE SEDIMENT FROM ENTERING SURFACE WATERS, INCLUDING CURB AND GUTTER SYSTEMS AND STORM SEVER INLETS. THE FOLLOWING MEASURES WILL BE TAKEN AS SEDIMENT CONTROL PRACTICES IN ORDER TO MINIMIZE SEDIMENTS FROM ENTERING

- INSTALLATION OF SEDIMENT CONTROL PRACTICES ON ALL DOWN
- INSTALLATION OF SEDIMENT CONTROL PRACTICES ON ALL DOWN
 GRADEEN PERMETERS PRICE TO LAND DISTURBING ACTIVITIES SITERET SWEEPING SHALL BE PERFORMED F VEHICLE TRACKING BMPS
 ARE NOT ADEQUATE TO PREVENT SEDIMENT TRACKING, TRACKED
 SEDIMENT MUST BE REMOVED FROM LIC PARED SHAPES SOTH ON AND
 OFFSITE WITHIN 24 HOURS OF DISCOVERY PER THE PERMIT.

-IF SEDIMENT CONTROL DEVICES SUCH AS SILT FENCE ARE FILLED TO 1/3 THE HEIGHT OF THE FENGE REMOVE ALL SEDIMENT WITHIN 24 HOURS OF DETECTION OR NOTIFICATION.

IF INLET PROTECTION DEVICES APPEAR PLUGGED WITH SEDIMENT, ARE FILLED TO 10 CAPACITY, OR HAVE STANDING WATER AROUND THEM, REMOVE THE SEDIMENT AND CLEAN OR REPLACE THE FILTER WITHIN 24 HOURS OF DETECTION OR NOTIFICATION.

JE THE GRAVEL CONSTRUCTION ENTRANCE/SVARE FILLED WITH SEDIMENT ETHER REPLACE THE ENTRANCE OR ADD ADDITIONAL GRAVEL WITH 24 HOURS OF DETECTION OR NOTIFICATION.

IF SEDIMENT FROM THE SITE IS OBSERVED ON ADJACENT STREETS OR OTHER IN SELVIZENT FROM THE SHE IS GISSERVED ON ADJACENT STREETS OR OTHER PROPERTIES, THE INSPECTOR SHALL IDENTIFY THE SOURCE AND DISCHARGE LOCATION OF THE SEDIMENT AND INSTRUCT TO IMPLEMENT ADDITIONAL EROSION AND SEDIMENT CONTROLS AT THOSE LOCATIONS TO PREVENT FUTURE DISCHARGES.

IF BUILDING MATERIALS, CHEMICALS, OR GENERAL REFUSE IS BEING USED, STORED, DISPOSED OF, OR OTHERWISE MANAGED INAPPROPRIATELY, CORRECT SUCH DEFECTS WITHIN 24 HOURS OF DETECTION OR NOTIFICATION. HE EXCESSIVE SEGMENTS OR DEBRIS ARE OBSERVED AT THE FLARED END SECTION OUTFALLS, THE INSPECTOR SHALL DETERMINE THE SOURCE AND DISCHARGE LOCATIONS OF SUCH MATERIALS. IF THE DISCHARGE HAS OCCURRED ON THE PROPERTY, REMOVE THE SEDIMENTS AND DEBRIS WITHIN 24 HOURS OF NOTIFICATION AND CORRECT THE SOURCE OF SUCH MATERIALS

AS DIRECTED BY THE INSPECTOR POLLUTION PREVENTION MEASURES

SOLID WASTE. INCLUDING BUT NOT LIMITED TO, COLLECTED ASPHALT AND CONGRETE MILLINGS, FLOATING DEBRIS, PAPER, PLASTIC, FABRIC, CONSTRUCTION AND DEBOLITION DEBRIS AND OTHER WASTE MUST BE DISPOSED OF PROPERLY AND MUST COMPLY WITH MPCA DISPOSAL.

INAZARDOUS MATERIALS INCLUDING BUT NOT TUMITED TO CIL, CASCILINE HAZARDOUS MATERIALO IS GUIDANCE BUT THE FOROMEN Y TORED INCLUDING SECONDARY CONTAINMENTS. TO PREVENT SHILLS LEAKS ON OTHER DISCHARGE RESTRICTED ACCESS TO STORAGE AREAS MUST EE PROVIDED TO PREVENT VANDALISM STORAGE AND DISPOSAL OF HAZARDOUS WASTE MUST BE IN COMPLIANCE WITH MICRA REQUILATIONS.

CONSTRUCTION EQUIPMENT/VEHICLES

EXTRINAL WASHING OF TRUCKS AND OTHER CONSTRUCTION VEHICLES MUST BE LIMITED TO A DEFINED AREA OF THE SITE. RUNOFF MUST BE CONTAINED AND WASTE PROPERLY DISPOSED OF. NO ENGINE DEGREASING IS ALLOWED ON SITE. REASONABLE STEPS TO PREVENT THE DISCHARGE OF SPILLED OR

LEAKED CHEMICALS SHALL BE TAKEN. ADEQUATE SUPPLIES MUST BE AVAILABLE AT ALL TIMES TO CLEAN UP DISCHARGED MATERIALS, CONDUCT FUELING IN A CONTAINED AREA UNLESS INFEASIBLE.

CONCRETE WASHOUT AREA

CONCRETE WASHOUT AREA CONCRETE CONTRACTOR SHALL FOLLOW ALL PERMIT REQUIREMENTS FOR CONCRETE WASHOUT, THE CONTRACTOR SHALL PROVIDE EFFECTIVE CONTRAINMENT FOR ALL LIQUID AND SOLID WASTES GENERATED BY WASHOUT DEPRATIONS. LIQUID AND SOLID TO THE CONTRAINMENT FOR ALL LIQUID AND SOLID WASTES GENERATED BY WASHOUT DEPRATIONS. LIQUID AND SOLID WASHOUT WASTES MUST NOT CONTACT THE GROUND AND THE CONTAINMENT MUST BE DESIGNED TO PROHIBIT RUNOFF FROM THE WASHOUT OPERATIONS/AREAS. LIQUID AND SOLID WASTES MUST BE DISPOSED OF PROPERLY AND IN COMPLIANCE WITH MPCA RULES. A SIGN MUST BE PROPERLY ADJACENT TO EACH WASHOUT FACILITY HAT REQUIRES SITE PERSONNEL TO UTILIZE THE PROPER FACILITIES FOR CONCRETE WASHOUT AND DISPOSAL OF WASHOUT WASTES. CONTRACTOR SHALL REVISE SWPPP TO INDICATE WASHOUT LOCATION ONCE THE LOCATION HAS BEEN

FERTILIZERS AND LANDSCAPE MATERIALS MUST BE LINDER COVER TO PREVENT THE DISCHARGE OF POLLUTANTS OR PROTECTED BY SIMILARLY EFFECTIVE MEANS DESIGNED TO MINIMIZE CONTACT WITH STORMWATER.

PORTABLE TOILETS MUST BE POSITIONED SO THAT THEY ARE SECURE AND WILL NOT BE TIPPED OR KNOCKED OVER - SANITARY WASTE MUST BE DISPOSED OF PROPERLY.

DEWATERING IS NOT ANTICIPATED TO BE REQUIRED. IN THE EVENT THAT DEWATERING IS NECESSARY CONTRACTOR SHALL COMPLY WITH PERMIT PART IV.D. REQUIREMENTS FOR DEWATERING.

THIS SWEED SHALL BE AMENDED BY THE CONTRACTOR IN ACCORDANCE WITH THE PERMIT AS NECESSARY TO INCLUDE ADDITIONAL REQUIREMENTS TO CORRECT PROBLEMS IDENTIFIED OR ADDRESS SITUATIONS PER PART III.B. OF

THE PROJECT MAY DISTURB 5 OR MORE ACRES THAT PROMOTE DRAIMAGE TO A COMMON LOCATION. THEREFORE A TEMPORARY SEDIMENT BASIN MAY BE REQUIRED. THIS SWPPP SHALL BE AMENDED BY THE CONTRACTOR IN ACCORDANCE WITH THE GENERAL FERMIT TO INCLUDE TEMPORARY SEDIMENTATION BASINS ISASINS SHALL BE GENERALED TO ACCUMONATE NO SEDMINITATION ISSUES, MASINS SHALL, BE DESIGNED TO ACCOMMODATE MO LESS THAN 300 CUBIC FEET OF LIVE STORAGE FER ACRE OF CONTRIBUTING DRAINAGE AREA BASIN OUTLETS SHALL BE DESIGNED TO WITHDRAW WATER FROM THE SURFACE OF THE BASIN, PREVENT SHORT-CIRCUTING AND THE DISCHARGE OF FLOATING DEBRIS, BASINS SHALL HAVE A STABILIZED EMERGENCY OVERFLOW LOCATION AND BE DESIGNED TO PREVENT THE DISCHARGE OF POLLUTANTS TO THE EXTENT PRACTICAL.

FINAL STABILIZATION

ALL PERVIOUS AREAS DISTURBED BY CONSTRUCTION AS DESIGNATED WILL RECEIVE VEGETATIVE COVER ACCORDING TO THE PLANS AND SCHEDULE. PINAL STABLE ACCORDING TO THE PLANS AND SCHEDULE. PINAL STABLE ACCORDING THE RESTORMED PERVIOUS AND SCHEDULE PINAL STABLE ACCORDING THE RESTORMED PERVIOUS AND SCHEDULE PERVIOUS AND S CONTROL BMPS (SUCH AS SILT FENCE) MUST BE REMOVED AS PART OF THE SITE FINAL STABILIZATION. ALL SEDIMENT MUST BE CLEANED OUT OF CONVEYANCES AND TEMPORARY SEDIMENTATION BASINS IF APPLICABLE NOTICE OF TERMINATION (NOT) MUST BE SUBMITTED WITHIN 30 DAYS OF FINAL

IMPAIRED WATERS, SPECIAL WATERS, AND

THIS PROJECT IS LOCATED WITHIN ONE MILE OF, AND ULTIMATELY DISCHARGES TO, AN IMPAIRED WATER. LAKE INDEPENDENCE IS LOCATED DIRECTLY NORTH OF THE PROJECT LOCATION AND IS LISTED AS IMPAIRED FOR AQUATIC CONSUMPTION AND AQUATIC RECREATION. DISCHARGE TO AN IMPAIRED WATER REQUIRES IMPLEMENTATION OF PARTS C.1 AND C.2 OF APPENDIX A OF THE PERMIT AS INCORPORATED INTO THIS SWPPP DOCUMENT

THE PROJECT WILL NOT TEMPORARILY IMPACT WETLANDS

SITE SOILS - SITE SOILS ARE SHOWN ON THIS SHEET. THIS PROJECT IS NOT LOCATED IN A KARST AREA.

SWPPP DOCUMENTS

THE SWEEP IS COMPOSED OF BUT NOT LIMITED TO THE BELOW PROJECT THE SWAPP IS COMPOSED OF, BUT NOT LIMITED TO, THE BELOW PROJECT STEE AT DOCUMENTS. THESE DOCUMENTS SHALL BE KEPT ON THE PROJECT SITE AT ALL TIMES THROUGHOUT CONSTRUCTION. THE SWAPP SHALL BE AMENDED BY THE PERSON RESPONSIBLE TO INCLUDE ANY DOCUMENTS NECESSARY TO ENSURE ADMERENCE TO THE GENERAL PERMIT.

BAKER RAVINE STABILIZATION CIVIL CONSTRUCTION DRAWINGS BY WENCH

RECORD RETENTION - THE SAPPP, ALL CHANGES TO IT, AND INSPECTION AND MAINTENANCE RECORDS MUST BE KEPT ON-SHEE DURING CONSTRUCTION, THE CONSTRUCTION DRAWNINGS ARE INCORPORATED HERBIR BY REFERENCE, AND A COPY OF THE PLAN SET SHOULD BE KEPT ON-SHE WITH THE SWPPP RECORDS. THE COMMEN MUST BEFAIN A COPY OF THE SWPPP ALONG WITH THE FOLLOWING RECORDS FOR THREE (3) YEARS AFTER SUBMITTAL OF THE NOTICE OF TERMINATION:

- NOTICE OF TERMINATION:

 ANY OTHER PREMITS REQUIRED FOR THE PROJECT:

 RICORDS OF ALL INSPECTION AND MAINTENANCE CONDUCTED DURING CONSTRUCTION:

 ALL PERMANENT OPERATIONS AND MAINTENANCE AGREEMENTS THAT HAVE BEEN MILE LIBERT OF MAINTENANCE, AGREEMENTS THAT HAVE BEEN MILE LIBERT OF MAINTENANCE, AGREEMENTS AND OTHER BINDING REQUIREMENTS REQUARDING PERPETUAL MAINTENANCE, SO FOR DESIGN OF THE TEMPORARY AND PERMANENT STORMMATER MAINTENANCE, AND THE MEMORY OF THE TEMPORARY AND PERMANENT STORMMATER MAINTENANCE, AND THE MEMORY STEEMS.



THE INSPECTION LOG WILL BE COMPLETED BY THE CONTRACTOR FOR THE CONSTRUCTION SITE THE MOMELTIAN LOG WILL BE COMPLETED BY THE CONTRACTOR FOR THE CONSTRUCTION SITE. INSPECTOR(S): TBD. TRAINING DOCUMENTATION (PER PART IV LEO FT THE PERMITY WILL BE INCORPORATED INTO THIS SWOPE AS SOON AS THE PERSONNEL. FOR THE PROJECT HAVE BEEN DETERMINED. THE CONTRACTOR WILL MAKE CORRECTIONS OR REPAIRS REQUIRED TO COMPLY THE FEBRAL.

INSPECTIONS AT THE SITE WILL BE COMPLETED IN ACCORDANCE WITH THE PERMIT AS FOLLOWS: ONCE EVERY SEVEN (7) DAYS DURING ACTIVE CONSTRUCTION AND. WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS.

THE INDIVIOUAL PERFORMING INSPECTIONS MUST BE TRAINED AS REQUIRED BY PART IV.E OF THE PERMIT. TRAINING DOCUMENTATION SHALL BE PROVIDED BY THE CONTRACTOR FOR INCORPORATION MITO THE SMOPP. INSPECTIONS MUST INCLUDE STRAILED AREAS, EROSION PREVENTION AND SEDMENT CONTROL BRIDGS. AND INFETENTION AREAS, CORRECTIVE ACTIONS WHAT THE INCIDENTED AND DATE OF CORRECTION MUST BE INCIDENTED AND EXTENT OF CORRECTION MUST BE NOTED AS IDENTIFIED IN SECTION IN.E. THE PERMIT, ANY OFFSITE DISCHARGE MUST BE DOCUMENTED AS IDENTIFIED IN SECTION IV.E.2.F OF THE PERMIT, ANY AMENDMENTS TO THE SWPPP PROPOSED AS A RESULT OF THE INSPECTION MUST. BE DOCUMENTED WITHIN SEVEN (7) CALENDAR DAYS. AN INSPECTION LOG IS ALSO ATTACHED. THE INSPECTION LOG AND SWIPP MUST BE KEPT ON-SITE FOR THE DURATION OF THE CONSTRUCTION.

AT A MINIMUM, THE FOLLOWING SHALL BE COMPLETED DURING EACH INSPECTION

RECORD DATE AND TIME OF INSPECTION. RECORD RAINFALL RECORDS SINCE THE MOST RECENT INSPECTION

HECORD MONEYAL RECORDS SINCE THE BUOST RECENT INSPECTION.
HASPECT THE SITE FOR EXCESS FORCION AND SEDIMENTATION.
HASPECT THE SITE FOR CEBRIS, TRASH, AND SPILLS.
HASPECT TEMPORARY ERGISION AND SEDIMENTATION CONTROL DEVICES.
HASPECT CONSTRUCTION ENTRANCES FOR SEDIMENT TRACKING ONTO PUBLIC STREETS. -RECORD RECOMMENDED REPAIRS AND MODIFICATIONS TO EROSION AND SEDIMENT CONTROLS. RECOMMEND ANY NECESSARY CHANGES TO THIS SWPPP.

-RECORD REPAIRS AND MODIFICATIONS IMPLEMENTED SINCE PREVIOUS INSPECTIONS.
-INSPECT THE ADJACENT STREETS AND CURB AND GUTTER FOR SEDIMENT, LITTER, AND CONSTRUCTION

THE GC MUST UPDATE THE SWPPP, INCLUDING THE JOBSITE BINDER AND SITE MAPS. TO REFLECT THE THE GU MIGHT OFFICE THE SWYPP, INCLUDING THE JUDGE IS BINDER AND STEE MAPS, TO BEFULL THE PROGRESS OF CONSTRUCTION ACTUTIES AND GENERAL CHANGES TO THE PROJECT STIT. UPDATES SHALL BE MADE DAILY TO TRACK PROGRESS WHEN ANY OF THE FOLLOWING ACTIVITIES OCCUR. BMP INSTALLATION, MOOPIFICATION OF REMOVAL, CONSTRUCTION ACTIVITIES (E.G. PAWING, SEMER INSTALLATION, ETC.), CLEARING, GRUBBING, GRADING, OR TEMPORARY AND PERMANENT STABILIZATION.

THE CONTRACTOR MAY UPDATE OR MODIFY THE SWPPP WITHOUT ENGINEER APPROVAL IN AN EMERGENCY SITUATION TO PREVENT SEDIMENT DISCHARGE OR PROTECT WATER QUALITY. THE CONTRACTOR IS ULTIMATELY RESPONSIBLE TO ENSURE COMPLIANCE WITH THE PERMIT AND PROTECTION OF DOWNSTREAM WATER QUALITY



MANAGEMENT


IZATION MN 55359 WATERSHED RAVINE STABILI TY RD 24 MAPLE PLAIN, PIONEER-SARAH CREEK WATE COMMISSION
3235 FERNBROOK LANE N PLYMOUTH, MN KER RA


PRELIMINARY

NOT FOR CO	NSTRUCTION
License #	Controller - 1
Date:	
Project #:	1508-000
Drawn By:	SJ
Issue Date	XXX
Have #	

C-201







MOVING FORWARD



SCHEDULE



CONSTRUCTION COST ESTIMATE

ITEM NO	ITEM	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL ESTIMATED COST
	BASE BID - Winter 2019 Construction				
1	Fall/Winter Mobilization and Demobilization	LS	1	\$ 19,500.00	\$ 19,500.00
2	Construct, Maintain, & Restore Site Access and Staging Areas	LS	1	\$ 7,000.00	\$ 7,000.00
3	Temporary Orange Safety Fence	LF	1125	\$ 4.00	\$ 4,500.00
4	Flotation Silt Curtain Type Moving Water - Maintained	LF	70	\$ 35.00	\$ 2,450.00
5	Sediment Control Log Type Straw (Or Bioroll) - Maintained	LF	1095	\$ 6.00	\$ 6,570.00
6	Inlet Protection - Maintained	EA	3	\$ 500.00	\$ 1,500.00
7	Culvert Protection - Maintained	EA	3	\$ 500.00	\$ 1,500.00
8	Construct and Maintain Temporary Sediment Basin	EA	1	\$ 1,000.00	\$ 1,000.00
9	Street Sweeper (With Pickup Broom)	HR	10	\$ 125.00	\$ 1,250.00
10	Tree Clearing & Grubbing	LS	1	\$ 25,000.00	\$ 25,000.00
11	Chip and Dispose of all Brush & Logs less than 6"	LS	1	\$ 10,000.00	\$ 10,000.00
12	Limb and Move Logs to Splitting Station (Logs >6")	LS	1	\$ 10,000.00	\$ 10,000.00
13	Remove & Dispose CMU's and Geogrid	CY	10	\$ 50.00	\$ 500.00
14	Woven ECB, Rolanka BioD-Mat 40	SY	2180	\$ 6.00	\$ 13,080.00
15	Non-Woven ECB Cat 3 Type Straw 2S (No Poly Netting)	SY	2180	\$ 3.00	\$ 6,540.00
16	Seeding	AC	0.5	\$ 2,500.00	\$ 1,250.00
17	Native Seed Mix	LB	20	\$ 50.00	\$ 1,000.00
18	Fescue Seed Mix	LB	100	\$ 2.50	\$ 250.00
19	Straw Mulch	TON	2	\$ 100.00	\$ 200.00
20	Temporary Sedimentation Basin - Maintained	LS	1	\$ 2,500.00	\$ 2,500.00
21	Class II Riprap Angular, No Limestone (Veg Riprap Toe)	TON	300	\$ 90.00	\$ 27,000.00
22	24" to 36" Fieldstone Boulders (Cross Vanes)	TON	110	\$ 110.00	\$ 12,100.00
23	MN DOT Type V, Non-Woven Geotextile Fabric	SY	4920	\$ 5.00	\$ 24,600.00
24	Class III Riprap, Angular, No Limestone (Spillways & Veg Riprap in-channel)	TON	705	\$ 90.00	\$ 63,450.00
25	Class III Riprap No Limestone (Veg Riprap & Outside Bend Toe Protection)	TON	1800	\$ 90.00	\$ 162,000.00

otal	Base	Bid	\$ 404,740.00

ITEM	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL ESTIMATED COST
BID Alt #1				
Class II Riprap Fieldstone	TON	70	\$ 90.00	\$ 6,300.00
	BID Alt #1	BID Alt #1	BID Alt #1	BID Alt #1


otal Bid Alt #1 \$ 6,300.00

ITEM NO	ITEM	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL ESTIMATED COST
	BID Alt #2				
27	Chip and Deliver all Brush & Logs less than 6" to Three Rivers Park District Nursery Facility	LS	1	\$ 10,000.00	\$ 10,000.00

Total Bid Alt #1 \$ 10,000.00

	SUBTOTAL	\$ 421,040.00
15%	CONTINGENCY	\$ 63,156.00
TOTAL	PROJECT BID	\$ 484,196.00

DISCUSSION









Responsive partner. Exceptional outcomes.